

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 07 1976

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Mayo of Red Tiger Drlg Co has this

date requested permission to plug the following described well:

Mr. Mayo guarantees payment of the plugging fee.

Operator's full Name: Glen N. Rupe

Complete Address: 925 OW Garvey Bldg 200 W Douglas Wichita, KS

Lease Name: Ball Well No. 1

Location: C SW/NW Sec. 5 Twp. 30s Rge. 12 (E)(W) W

County: Barber Total Depth 4742 Oil Well

Gas Well  Input Well  SWD Well  D & A  ~~Non-Producing~~ OWWO

Mr. Mayo was instructed to plug the well as follows:

305 ft 8 5/8 surface cement circulated. Pump plug, 35 sacks

cement to 300 ft. Mud to 40 ft, plug, 1/2 sack hulls, 15

sacks cement to surface. 5 sacks cement in rat hole.

Pumped by Halliburton Cementing Great Bend, KS

Very truly yours,

[Signature]  
Conservation Division Agent

*CPA*