

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 30 1960
 9-30-63

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Bill Shipley of Graybol Oil Corporation has this

date requested permission to plug the following described well:

Mr. Shipley guarantees payment of the plugging fee.

Operator's full Name: Graybol Oil Corporation

Complete Address: 2200 Nat'l Bank of Tulsa, Tulsa, Oklahoma

Lease Name: Coss Well No. # 1

Location: NE SE Sec. 1 Twp. 30 Rge. 12 (E) (W) W

County Barber Total Depth 4813 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Shipley was instructed to plug the well as follows:

271' of 8 5/8" surface pipe, cemented with 165 sacks.

Fill hole with drilling mud to 265, 1st cementing plug,

1/2 sack hulls, cement with 25 sacks. Fill hole with drill-

ing to 40', 2nd cementing plug, 1/2 sack hulls, cement with

10 sacks to base cellar. Bridge and cement rat hole with 2
sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent