

State of Kansas



15-007-10032-0000

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 9 1963
7963
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Buck Hall of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Aylward Drilling Co.

Complete Address: 909 1st National Bank Bldg., Wichita, Ks.

Lease Name: Whelan Well No. # 2

Location: C NW SW Sec. 29 Twp. 31 Rge. 11 (E) (W) W

County Barber Total Depth 4,358 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hall was instructed to plug the well as follows:

125' of 8 5/8" surface pipe, cement circulated. 4325' of

5 1/2" long string. Sand to 4315', cement with 5 sacks.

Fill hole with mud to 185', 10' rock bridge, cement with 25

sacks. Fill hole with mud to 40', 10' rock bridge, cement

with 10 sacks, to base cellar.

Very truly yours,

Archie Fleming
Conservation Division Agent