

1 040325

9-27 40-02 145

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,367-8
C N/2 NW, SEC. 18, T 30 S, R 13 W/EX

TECHNICIAN'S PLUGGING REPORT

4620 feet from S section line
3960 feet from E section line

Operator License # 5255

Lease Name Minnie Smith Well # 1

Operator: McGinness Oil Company

County Barber 155.09

Name & Address 1026 Union Center Building
Wichita, KS 67202

Well Total Depth 4772 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 372

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:45 a.m. Day: 27 Month: 9 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4770' PBD 4729' Perfs at 4536-4544' Elevation 1890' GL
1st plug sand back to 4500' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 10:30 a.m. Day: 27 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4500' and dumped 5 sx cement on top of
sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 50 psi and shut in 0 psi. Well on vacuum.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3100' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

INVOICED

DATE 10-4-89

INV. NO. 26018

observe this plugging.

Signed Stephen J. Peifer
(TECHNICIAN)