

OB

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 54-11

LOCATION C 7E-7W

SEC 30 TWP 31 RGE 11W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Williams

Operator Solar Oil Co Address 1117 W. North St. Bldg. Wichita Kansas.

Field _____ County Becker

Total Depth 4697 Feet.

Plugging Contractor Ace Pipe Pulling Co

Plugging Contractor's License No. 2

Address Great Bend, Kansas.

(Describe briefly the manner in which the well was plugged)

10 3/4" 97' C.W.C. 5 1/2" 4314' cut 50 ft.
hole filled with sand to 4300' run 5' of
Cement with dump filter. Mud to 260' set
rock fudge run 15' of Cement. Mud to 97'
rock fudge 15' of Cement. Mud to 25' set fudge
10' of Cement hole circulated with heavy
gell mud through 5 1/2" with Pump.

M. L. Rice
District Conservation Agent

Date 4-24-56

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1956
4-26-56
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 30 T 31 R 11W
BOOK PAGE 54 LINE 11