

CPB
R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 40-28 County: Barber
Location: CNW NE Sec. 30 Twp. 31 Rge. 11 (E) (W)
Name of Field: _____ Total Depth: 4360

I have this date completed supervision of plugging of:

Lease Name: Nuckolls "B" Well No. 2
Operator's Full Name: Agnew Drilling Co.
Complete Address: 813 First National Bank Bldg., Wichita Kans.
Plugging Contractor: West Supply Co.
Address: Chase Kans. License No. 14

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 11 AM Day 7 Month June Year 1959

The above well was plugged as follows:

108' of 8" surface casing. Open hole from 4327' to 4360'.
Hole was worked to 4315 with 5 sack cement dumped with
drip hole. Pulled 3710 of 5 1/2" production pipes. Hole filled
to 160' with heavy mud. Rock bridge from 160' to 150'.
30 sack cement placed top bridge. Mud to 40'. 10' Pack
bridge from 40' to 30'. 10 sack cement placed top bridge
to base of collar.

Signed: [Signature]
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

PLUGGING
FILE SEC 30 T. 31 R 11W
BOOK PAGE 40 LINE 28

6-10-59
CONSERVATION DIVISION
Wichita, Kansas