

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1965
9-30-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Lario Oil & Gas Company
Complete Address: 301 South Market, Wichita, Kansas
Lease Name Nuckolls Well No. # 4
Location SE NW SE Sec. 30 Twp. 31 Rge. 11 (E) (W) W
County Barber Total Depth 4295'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Glen & Smith Casing Pulling Company
Address: Box 156, Ellinwood, Kansas License No. 396
Operation Completed: Hour 3:30 PM Day 28th Month Sept. Year 1965

The Above well was plugged as follows:

149' of 8 5/8" surface pipe, cemented with 100 sacks. 4285' of 5 1/2" long
string, temperature survey 2727'. Plug back to 4260'. Top perforation
3546'. Bottom plug was pushed to 3530', 50' of sand bridge, and cemented
with 5 sacks. 2500' of 5 1/2" long string was recovered from the hole.
Fluid in the hole was bailed down to 200', bridge plug and rock bridge
from 200' to 190', and cemented with 25 sacks, bringing the top of the cement
to 135' in the surface pipe. Hole was filled with mud to 40', bridge of rock
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 9/30/65
INV. NO. 1897-W