

15-007-01331-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

SEP 27 1965
9-27-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Lario Oil & Gas Company

Complete Address: 301 South Market, Wichita, Kansas

Lease Name Nuckolls Well No. # 3

Location N/2 N/2 SE Sec. 30 Twp. 31 Rge. 11 (E) (W)W

County Barber Total Depth 4325'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 2:15 PM Day 24th Month Sept. Year 1965

The Above well was plugged as follows:

139' of 8 5/8" surface pipe, cemented with 100 sacks. 4306' of 5 1/2" long
string, temperature survey at 2710'. Top perferation 3362'. Bottom plug
was pushed to 3375', and 50' of sand bridge, and cemented with 5 sacks.
2680' of 5 1/2" long string was recovered from the hole. Fluid in the hole
was bailed down to 215', bridge plug and rock bridge from 215 to 200',
and cemented with 15 sacks. Hole was filled with mud to 145', rock bridge
from 145 to 140', and cemented with 10 sacks. Hole was filled with mud to
40', rock bridged from 40' to 30', and cemented with 10 sacks to the base
of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 9/27/65
INV. NO. 1868-U