

To: 1 040471
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-4
API NUMBER 15- NA 15 007-10285-0000

NE NE SW, SEC. 12, T 33 S, R 13 W/E

2310 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519

Lease Name Cinda Well # 1

Operator: Chevron U S A, Inc.

County Barber 15/12

Name & Address P.O. Box 12116

Well Total Depth 4650 feet

Oklahoma City, OK 73157

Conductor Pipe: Size feet

Surface Casing: Size 16" feet 262

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS

Company to plug at: Hour: 8 a.m. Day: 4 Month: 10 Year: 19 90

Plugging proposal received from Owen Lang

(company name) Chevron U S A, Inc. (phone) 713-561-3826

were: 8 5/8" at 4446' w/800 sx cement, 7" liner at 4626' to surface, PBTD 4645'

Perfs at 4547-68'

1st plug set cement retainer at 4440', load hole with gel,

2nd plug pump 60 sx cement through cement retainer and put 5 sx cement on top of retainer.

3rd plug perforate 8 5/8" casing at 620', pump 390 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 4 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT Set cement retainer at 4440', loaded hole with gel, pumped 60

sx cement through cement retainer and put 5 sx cement on top of retainer, Class A cement.

Perforated 8 5/8" casing at 620', broke circulation with weight. Pumped 390 sx 65/35

6% gel cement down 8 5/8" casing at 4 BPM at 75#. Cement circulated out 8 5/8"/16" annulus.

Remarks: Cemented by B.J. Services. Recovered 2776' of 7" casing. 10-8-90

INVOICED

(If additional description is necessary, use BACK of this form. 1990)

I (did / ~~did not~~) observe this plugging.

DATE 10-18-90
SER. NO. 29651

Signed Stephen J. Pfeifer (TECHNICIAN)