

041264

9-4

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-007-21,170-0000  
SE NW SW, SEC. 10, T 33 S, R 13 W/E  
1650 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # \_\_\_\_\_  
Operator: Kansas Corporation Commission  
Name: \_\_\_\_\_  
Address: 130 S. Market, Rm. 2078  
Wichita, KS 67202

Lease Name Thompson Well # 1  
County Barber  
Well Total Depth 4700 Est. \_\_\_\_\_ feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated never produced

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 4 Month: 9 Year: 19 97

Plugging proposal received from Richard Lacey

(company name) KCC (phone) 316-338-1610

were: 4 1/2" casing and perforations--unknown depth, PBTD 3160'

1st plug sand back to 3350' and dump 4 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 4 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 2930' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2450' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Stephen J. Pfeiffer  
(TECHNICIAN)