

1 040499

1-17

184 P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-20,586-2-00-01

C NW NE, SEC. 23, T 31 S, R 11 W/E
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3372

Lease Name Cargill "OWWO" Well # 1

Operator: Morrison-Dixon Oil Operations, Inc.
Name & Address: 100 N. Main, Suite 801
Wichita, KS 67202

County Barber 101.72

Well Total Depth 3130 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 1-31-91
JAN 31 1991 105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12 p.m. Day: 17 Month: 1 Year: 19 91

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 3116' w/125 sx cement, PRTD 2982', Perfs at 2989-96, 2960-64'

1st plug sand back to 2900' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 p.m. Day: 17 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 2910' and dumped 4 sx cement on top of
sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 900 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (copy to MORRISON-DIXON) observe this plugging.

FEB 13 1991

DATE _____

INV. NO. 30706

Signed Stephen J. Pfeiffer
(TECHNICIAN)

15-007-20586-00-01



WIRE-TECH

GAMMA RAY BOND LOG

COMPANY MORRISON-DIXON OIL OPERATIONS

WELL CARGILL #1

FIELD

COUNTY BARBER STATE KANSAS

Location

Other Services:

NW-NE RECEIVED
STATE COMPOSITION COMMISSION
11-7-90
NOV 07 1990
31s Rge 11w

Sec. 23 Twp 31s Rge 11w

Permanent Datum GROUND LEVEL CONSERVATION DIVISION
Log Measured From KELLY BUSHING Wichita, Kansas
Drilling Measured From KELLY BUSHING Perm Datum

Elev. KB 1785'
DF
GL 1775'

Date 9-12-90
Run No ONE
Depth-- Driller
Depth-- Wire Tech 3079'
Btm Log Inter 3078'
Top Log Inter 2600'
Type Fluid in Hole WATER
Fluid Level FULL
Date Cemented
Type of Cement
Log Top of Cement 2738'
Max Rec Temp °F @
Equip. Location 52 GREAT BEND, KANSAS
Recorded By BRENT CURTIS
Witnessed By

RUN		BORE-HOLE RECORD		CASING RECORD			
NO	BIT	FR. M	TO	SIZE	WEIGHT	FROM	TO
	12 1/4	0'	256'	8 5/8		0'	256'
	7 7/8	256'	4570'	4 1/2		0'	