

2 090023

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 077-21,009-0000

, SEC. 28, T 34 S, R 6

1650 feet from N/E section line

4950 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5630

Lease Name Roach Well # 1

Operator: Brandt Production Co.

County Harper

Name & Address 1200 Douglas Bldg

Well Total Depth 5285 171.76 feet

104 S. Broadway

Conductor Pipe: Size feet

Wichita, Ks. 67202

Surface Casing: Size feet

Abandoned Oil Well Gas Well Input Well SWD Well D&A XX

Other well as hereinafter indicated

Plugging Contractor Brandt Drilling Co., Inc. License Number 5840

Address 1200 Douglas Building, Wichita, Ks.

Company to plug at: Hour: 7:00a.m. Day: 15th Month: 7 Year: 19 84

Plugging proposal received from

(company name) K.C.C., Salina, Ks. (phone)

were: 35 sacks at 3700'; 35 sacks at 950'; 35 sacks at 320'; 10 in rat
10 in mouse

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1984

CONSERVATION DIVISION Plugging Proposal Received by Toman
Wichita, Kansas (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XX

Operations Completed: Hour: 6:00a.m. Day: 17 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT Filled hole with heavy mud; run drill pipe to 3700'; spotted 35 sacks cement through drill pipe; pulled drill pipe to 950'; spotted 35 sacks cement through drill pipe; pulled drill pipe to 320'; spotted 35 sacks cement through drill pipe; pulled drill pipe to 60'; spotted 25 sacks cement through drill pipe on top of a wood and rubber plug. Run one joint of drill pipe in rat, circulated 10 sacks cement to surface, Run one joint of drill pipe in mouse hole; circulated 10 sacks cement to surface.

Remarks: Sun Cement Ticket #18120

(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 7-31-84

Signed David Wertz (TECHNICIAN)

INV. NO. 2781

UK

RR