

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

4-24

2-040879

API NUMBER: 15-077-211620001

C-SE-SE, SECTION 19 TOWNSHIP 34 RANGE 6W

OPERATOR LICENSE # 31434 660 FEET FROM S SECTION line  
OPERATOR L & J Oil Properties 660 FEET FROM E SECTION LINE  
NAME & 150 N. Main Ste 150  
ADDRESS Wichita Ks. 67202

LEASE NAME: Whisman #1  
COUNTY: Harper  
WELL TOTAL DEPTH: 4865 158.11  
PIPE: 4 1/2 @ 4862  
SURFACE CASING: 8 5/8 @ 217

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A X

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Clarke Corp.

ADDRESS: Medicine Lodge Ks. LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: Alan Vitral

COMPANY NAME: Clarke Corp. PHONE: \_\_\_\_\_

WERE: PBSD 4832 Sand to 46522 @ 4 sks.  
Perfs. 4672-4700 35 sks @ 1200  
35 sks @ 800  
Circ. Cmt. 276-0

PLUGGING PROPOSAL RECEIVED BY: \_\_\_\_\_

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE ( X )

COMPLETED: HOUR: 1445 DAY: 24 MONTH: 4 YEAR: 1997

ACTUAL PLUGGING REPORT: The Perfs. were covered with sand from 4832' to 4605'. The 4 1/2 was recovered from 3700' and pulled to 1210' where 35 sks of cement was spotted. The 4 1/2 was pulled to 814' where 35 sks. of cement was spotted. The 4 1/2 was pulled to 276' where cement was circulated to surface. The remaining 4 1/2 was pulled from the wellbore and the cement was topped off.

REMARKS: Allied Cement 60/40 4% gel

INVOICED

RECEIVED  
KANSAS CORPORATION COMMISSION I DID NOT OBSERVE THIS PLUGGING.

DATE 4-28-97  
INV. NO. 48023

APR 25 1997

Signature  
STEVE VANGIESON

CONSERVATION DIVISION  
WICHITA, KS