

1080210

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,774-0000

SW SW _____, SEC. 26 _____, T 31 _____ S, R 11 _____ WXB
N SE Corner of
590 _____ feet from ~~XXX~~ section line
W SE Corner of
4530 _____ feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____ 5171

Lease Name Chapin-Smith Well # 1

Operator: TXO Production Corp.

County Barber

Name & Address 200 West Douglas, Suite 300

Well Total Depth 3930 127.73 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 7:00 am Day: 6 Month: September Year: 1984

Plugging proposal received from Norman Vorh

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 3911' Perfs at 3764-70 & 3747-52

1st plug sand back to 3700' and dump 4 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 100 sx cement.

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00 am Day: 6 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 3911' Perfs at 3764-70' & 3747-52'

1st plug sanded back to 3700' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and

100 sx cement.

Maximum pressure 750 psi and shut in pressure 200 psi

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1984
9-17-84

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Cemented by Sun

(If additional description is necessary, use BACK of this form.)

(If ~~possible~~ observe this plugging.)

INVOICED

DATE 9-20-84

INV. NO. 3800

Signed J. H. Metz SD
(TECHNICIAN)