

RECEIVED

MAY 20 2002
5-20-02
KCC WICHITA

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-077-20,209-0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR McCoy Petroleum Corporation KCC LICENSE # 5003 *6/02*
(owner/company name) (operator's)

ADDRESS 453 S. Webb Rd P.O. Box 780208 CITY Wichita

STATE Kansas ZIP CODE 67278 CONTACT PHONE # (316) 636-2737

LEASE Truby "A" OWWO WELL# 1-31 SEC. 31 T. 33S R. 7 (East West)

SE - SE - NW - SPOT LOCATION/QQQQ COUNTY Harper

3165 FEET (in exact footage) FROM SYN (circle one) LINE OF SECTION (NOT Lease Line)

3190 FEET (in exact footage) FROM EYW (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL X GAS WELL ___ D&A ___ SWD/ENHR WELL ___ DOCKET# ___

CONDUCTOR CASING SIZE ___ SET AT ___ CEMENTED WITH ___ SACKS

SURFACE CASING SIZE 8-5/8 SET AT 268 CEMENTED WITH ___ SACKS

PRODUCTION CASING SIZE 4-1/2 SET AT 4714.50 CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4652' - 4672'

ELEVATION 1389' 1394' T.D. 4720 PSTD 4660 ANHYDRITE DEPTH ___
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR ___ CASING LEAK ___ JUNK IN HOLE ___

PROPOSED METHOD OF PLUGGING Set CIBP or sand to 4600'. Pull stretch and cut casing.

Pull csg to 1500', spot 35 sx cement. Pull csg to 1000', spot 35 sx cement. Pull csg to

320', circulate cement to surface. 60/40 cement, 4% gel. (5 sx f/ sand; 1 sk f/ CIBP)

Pull csg & top (If additional space is needed attach separate page)
off cement.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes

If not explain why? Well was a washdown. No Copies

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE# () 620-272-1296

ADDRESS P.O. Box 39 City/State Spivey, KS 67142

PLUGGING CONTRACTOR Shawnee Well Service KCC LICENSE # 30346 *3/03*
(company name) (contractor's)

ADDRESS Attica, KS 67009 PHONE # (620) 243-4457

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 5/17/02 AUTHORIZED OPERATOR/AGENT: Scott Hampel
(signature)



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

McCoy Petroleum Corporation
453 S. Webb Rd. STE 310
PO Box 780208
Wichita, KS 67278-0208

May 23, 2002

Re: TRUBY A OWWO #1-31
API 15-077-20209-00-01
SENW 31-33S-7W, 3165 FSL 3190 FEL
HARPER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #2
130 S. Market, Room 2125
Wichita, KS 67202-3208
(316) 337-6231