

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

f

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -007 -3096-0000 (of this well)

Operator's Full Name Howers Drilling Co.

Complete Address Vickers-KSB&T Bldg., Wichita, Ks. 67202

Lease Name Durell Well No. 1

Location C NE NW Sec. 21 Twp. 31s Rge. 11(E) (W) X

County Barber Total Depth 4558

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Clarke Corp.

Address 107 W. Fowler, Medicine Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 10:45 Am. Day 23 Month 1 Year 1980

The above well was plugged as follows:

363' 8 5/8" casing w/300 sax cement. 4 1/2" casing set at 3908' w/150  
sax cement. Plug back to 3862'-Preforated at 3780'-Sand back to 3755'  
top sand w/4 sax mixed cement w/dump bailer-Pull 3140' 4 1/2" casing-  
Build bridge at 300'-Dump 2 1/2 yard grout in 8 5/8" casing back to "0".  
(Grout bridged off at 175')Medicine Lodge Ready Mix.

RECEIVED  
1-25-80  
JAN 25 1980

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

**INVOICED**  
DATE 1-25-80  
INV. NO. 1402-w

15-007-38196-0000

WELL LOG

COMPANY:	Bowers Drilling Company, Inc.
CONTRACTOR:	Bowers Drilling Company, Inc.
FARM:	Durell #1
LOCATION:	C NE NW Section 21-31S-11W Barber County, Kansas
COMMENCED:	May 3, 1965
COMPLETED:	May 15, 1965
ELEVATION:	1761 Kelly Bushing

0 - 675	Redbed	8-5/8" casing set at 363' with 300 sacks
675 - 1545	Redbed, shale and shells	
1545 - 2045	Shale and shells	
2045 - 3793	Lime and shale	
3793 - 3900	Sand and shale	
3900 - 4020	Lime and shale	
4020 - 4430	Lime	
4430 - 4484	Lime and shale	
4484 - 4517	Lime	
4517 - 4530	Miss. chert	
4530 - 4558	Lime and chert	4 1/2" casing set at 3908 with 150 sacks
4558	T. D.	

LOG TOPS:

Elgin Zone	3576	2nd Douglas Sand	3845
Heebner	3710	Lansing	3906
1st Douglas Sand	3778	Mississippian	4501

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the Durell #1 located C NE NW Section 21-31S-11W, Barber County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

*Emil E. Bowers*

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 3rd day of June, 1965.

RECEIVED Donna F. Miller, Notary Public  
 STATE CORPORATION COMMISSION

My commission expires May 1, 1966

JAN 14 1966  
 1-14-80  
 CONSERVATION DIVISION  
 Wichita, Kansas