

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
JUL 1 1966
7-1-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Western Oil Fields, Inc.

Complete Address: P. O. Box 1137, Hobbs, New Mexico

Lease Name Chain Well No. # 1

Location SE SE SE Sec. 21 Twp. 31 Rge. 11 (E) (W) W

County Barber Total Depth 4496'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 3:15 PM Day 29th Month June Year 1966

The Above well was plugged as follows:

223' of 8 5/8" surface pipe, cemented with 140 sacks. 4495' of 5 1/2" long
string, cemented with 250 sacks. Plug back T. D. 3800'. Top perforation
3749'. Bottom of the hole was sanded to 3725', and cemented with 5 sacks,
through the dump bailer. 2500' of 5 1/2" long string was recovered from the
hole. Fluid in the hole was bailed down to 220', rock bridge from 220' to
210', and cemented with 25 sacks. Hole was filled with mud to 40', rock
bridge from 40' to 30', and cemented with 10 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 7/1/66
INV. NO. 3493-W