

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1966
11-14-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Ben F. Taylor
Complete Address: 2809 Northwest Expressway, Oklahoma City, Oklahoma
Lease Name Denton Well No. # 1
Location App. C SW NE Sec. 30 Twp. 34 Rge. 6 (E) (W) W
County Harper Total Depth 5230'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Gabbert-Jones, Inc.
Address: 830 Sutton Place, Wichita, Kansas License No.
Operation Completed: Hour 9:00AM Day 7th Month Nov. Year 1966

The Above well was plugged as follows:

297' of 8 5/8" surface pipe, cement circulated with 250 sacks. Hole
was filled with drilling mud to 280', 1st cementing plug, bridged with
1/2 sack of hulls on fluid at 280', and cemented with 25 sacks. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2
sack of hulls on fluid at 40', and cemented with 10 sacks to the base
of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11/15/66
INV. NO. 4265-W

Signed: Archie Elving
Well Plugging Supervisor