

Form CP-3  
Rev. 6-26-62

*26*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Intent to Drill,  
filed March 28, 1967.

APR 17 1967

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name J. R. Butler  
Complete Address: 2138 Bank of Southwest Bldg., Houston, Texas 77002  
Lease Name Charlie Carr Well No. # 1  
Location C NW NW Sec. 23 Twp. 34 Rge. 7 (E) (W) W  
County Harper Total Depth 5155'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated:       
Plugging Contractor: Corbett Drilling Company  
Address: Box 3525, Utica Square, Tulsa, Oklahoma License No.       
Operation Completed: Hour 8:00PM Day 14th Month April Year 1967

The Above well was plugged as follows:

262' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole was  
filled with drilling mud to 250', 1st cementing plug, bridged with 2 sacks  
of dry cement and 1/2 sack of hulls on fluid at 250', and cemented with 23  
sacks. Hole was filled with drilling mud to 40', 2nd cementing plug, bridge  
with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40', and cemented  
with 9 sacks to the base of the cellar. Rat and mouse holes bridged and  
cemented with 5 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/17/67  
INV. NO. 5052-W