

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 8 1967
5-8-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued May 3, 1967.

Operator's Full Name Solar Oil Company

Complete Address: 1117 Union National Bldg., Wichita, Kansas 67202

Lease Name R. L. Nuckolls Well No. # 4

Location C S/2 S/2 NE Sec. 30 Twp. 31 Rge. 11 (E) (W) W

County Barber Total Depth 4340'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 3:30PM Day 6th Month May Year 1967

The Above well was plugged as follows:

150' of 8 5/8" surface pipe, cemented with 135 sacks. 4323' of 5 1/2" long
string, cemented with 200 sacks. Plug back T.D. 3800'. Top perferation
3561'. Bottom of the hole was sanded to 3550', and cemented with 5 sacks,
through the dump bailer. 3045' of 5 1/2" long string was recovered from the
hole. Hole was circulated with heavey rotary mud at 1300'. 15 sacks of
Gel-Mud and 100 sacks of cement was pumped into the surface pipe, through
8 5/8" swage, to a pressure of 150 lbs. A wiping plug was run between
the Gel-Mud and the cement. This cementing was done by Halliburton Cementing
Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elving
Well Plugging Supervisor

DATE 5/11/67

INV. NO. 5180-W