

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

FEB 02 1977
2-2-77
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-007-10043-0000 (of this well)

Operator's Full Name Aylward Drilling Company
Complete Address 909 First National Bank Building Wichita, KS
Lease Name Swartz 2 Well No. A-1
Location SE SE SE Sec. 30 Twp. 31 Rge. 11 (D) (W) X
County Barber Total Depth 4317
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pelling
Address Box 176 Chase Kansas License No. 683
Operation Completed: Hour 1:30 pm Day 31 Month Jan Year 1977

The above well was plugged as follows:
116' of 12 1/2" surface, 4302 of 7" long string,
sand back to 4275, 6 SKs cement with boiler, 1600' of
7" recovered, at 640' pumped 20 SKs Gel. through 7", pulled
11 joints, spotted 175 SKs cement with #9 Gel through 7"
at 300', pulled 5 joints spotted 25 SKs through 7" at 150'
spotted 60 SKs cement through 7" at 60' pulled 2 joints,
cement to surface. 7" long string pulled into at 1600'
pumped by Allied Cement Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: J. J. McG
Well Plugging Supervisor

DATE 2-2-77
NO. 4575-W