

1041397

TO:
STATE CORPORATION COMMISSIONAPI NUMBER 15-007(90.319) 15-007-30042-00-01
C NE NE SEC. 20, T 31 S, R 11 WCONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINEWICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WATKINS "A" WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY BARBER 146.25OPERATOR LICENSE # 31142WELL TOTAL DEPTH 4500 FEETOPERATOR: PETROLEUM PROPERTY SERVICES PRODUCTION CSG: SIZE 4 1/2" @ 4314' WITH 200 SXNAME AND 155 N MARKET #1010SURFACE CASING: SIZE 8 5/8" @ 359' WITH 300 SXADDRESS WICHITA, KS 67202-1824ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D-21,619 D/AOTHER WELL AS HEREINAFTER INDICATED PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105ADDRESS PO BOX 187, MEDICINE LODGE, KS 67104COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 13 MONTH: 06 YEAR: 2000PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665WERE: PERFS AT 3553-63SET CIBP @ 3450' AND PUT 2 SX CEMENT ON TOP OF CIBP THROUGH DUMP BAILER. PUMP DOWN 8 5/8"SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8"WIPER PLUG AND 100# CEMENT. MAXIMUM PSI = 700#. SHUT IN PRESSURE = 500#.PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFERPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE OPERATIONS COMPLETED: HOUR: 10:15 AM DAY: 13 MONTH: 06 YEAR: 2000ACTUAL PLUGGING REPORT SET CIBP @ 3450' AND PUT 2 SX CEMENT ON TOP OF CIBP THROUGH DUMP BAILER. PUMP DOWN 8 5/8"SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8"WIPER PLUG AND 100 SX CEMENT. MAXIMUM PSI = 700#. SHUT IN PRESSURE = 500#.REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2500' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 6/16/00SIGNED Steve Pfeifer

(TECHNICIAN)

FORM CP-2/3

INV. NO. 2000061874

INVOICED