

1070112

RECEIVED

STATE CORPORATION COMMISSION

15-007-10007-0001

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

API NUMBER 15-007-70-390
SW NW NE SEC. 20, T 31 S, R 11 W

JAN 06 2000
1-6-00

CONSERVATION DIVISION SECTION 4290 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WATKINS WELL # 1

TECHNICIAN'S PLUGGING REPORT 12/30

COUNTY BARBER

OPERATOR LICENSE # 31142

WELL TOTAL DEPTH 3835 FEET

OPERATOR: PETROLEUM PROPERTY SERVICES INC PRODUCTION CSG: SIZE 4 1/2" @ 3819' WITH 100 SX

NAME AND 155 N MARKET #1010 SURFACE CASING: SIZE 8 5/8" @ 331' WITH 250 SX

ADDRESS WICHITA, KS 67202-1824

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187, MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 2:50 PM DAY: 30 MONTH: 12 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 3698-3708

1ST PLUG SET CIBP AT 3590' WITH 2 SX CEMENT. 2ND PLUG RUN TUBING TO 600', SPOT 50 SX
CEMENT WITH 3% CC. 3RD PLUG PULL TUBING TO 330' CIRCULATE CEMENT TO SURFACE. GOOD
CIRCULATION THROUGHOUT JOB.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 3:35 PM DAY: 30 MONTH: 12 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 3590' WITH 2 SX CEMENT. 2ND PLUG RUN TUBING TO 600', SPOT 50 SX
CEMENT WITH 3% CC. 3RD PLUG PULL TUBING TO 330' CIRCULATE CEMENT TO SURFACE. GOOD
CIRCULATION THROUGHOUT JOB.

INVOICED

DATE 1/10/00

INV. NO. 061092

REMARKS: USED 60/40 POZMIX 6% GEL 1/2" FLO SEAL BY ALLIED. RECOVERED 2600' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED [Signature]
(TECHNICIAN) FORM CP-2/3