

1070137

15-007-10335-00 00

TO: STATE CORPORATION COMMISSION

API NUMBER DRILLED SEPTEMBER 1943
C NW SEC. 30, T 33 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 3960 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3960 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ANGEL A WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY BARBER 163,41

OPERATOR LICENSE # 6006

6/27

WELL TOTAL DEPTH 5028 FEET

OPERATOR: MOLZ OIL COMPANY PRODUCTION CSG: SIZE 7" @ 5023' WITH 650 SX

NAME AND 19159 SW CLAIRMONT SURFACE CASING: SIZE 10 1/4" @ 291' WITH SX

ADDRESS KIOWA, KS 67070-8801

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187, MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 9:15 AM DAY: 06 MONTH: 03 YEAR: 2000
HOUR: 12:30 PM DAY: 27 MONTH: 06 YEAR: RECEIVED

STATE CORPORATION COMMISSION

PLUGGING PROPOSAL RECEIVED FROM RON MOLZ

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

JUN 30 2000
6-30-00

WERE: PERFS AT 4565-70

CONSERVATION DIVISION
Wichita, Kansas

1ST PLUG PUMP 25 SX CEMENT AND 50# HULLS AT 4500' THROUGH 2 3/8" TUBING. 2ND PLUG PUMP 50

SX CEMENT AT 900'. 3RD PLUG SPOT 50 SX CEMENT AT 300'. 4TH PLUG SPOT 20 SX CEMENT AT 0-30'

GOOD CIRCULATION THROUGHOUT JOB. USED 60/40 6% BY ALLIED. ON 06/27/00 PUMPED 2 SX COMMON

CEMENT DOWN 10 1/4 X 7" ANNULUS BY ACID SERVICES. PRESSURED TO 300#.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 12:45 PM DAY: 06 MONTH: 03 YEAR: 2000
HOUR: 1:00 PM DAY: 27 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT _____

1ST PLUG PUMP 25 SX CEMENT & 50# HULLS AT 4500' THROUGH 2 3/8" TUBING. 2ND PLUG PUMP 50 SX

CEMENT AT 900'. 3RD PLUG PUMP 50 SX CEMENT AT 300'. 4TH PLUG PUMP 20 SX CEMENT AT 0-30'.

GOOD CIRCULATION THROUGHOUT JOB. USED 60/40 6% GEL BY ALLIED. ON 06/27/00 PUMPED 2 SX COMMON

CEMENT DOWN 10 1/4 X 7" ANNULUS BY ACID SERVICES. PRESSURED TO 300#.

REMARKS: USED 60/40 6% GEL BY ALLIED & COMMON CEMENT BY ACID SERVICES. NO CSG. RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED
DATE 7/10/00
SIGNED _____
NO. 1060035

(TECHNICIAN) [Signature]

FORM CP-2/3

[Signature]