

To: 1 040466  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-13  
API NUMBER 15- 007-10,334-0000  
C NE, SEC. 20, T 33 S, R 13 W/E  
3960 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519

Lease Name Lasswell Well # 2

Operator: Chevron U.S.A. Inc.

County Barber 164.84

Name & Address P.O. Box 36366

Well Total Depth 5072 feet

Houston, TX 77236

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 296

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Dunnam Well Service License Number 9678

Address 130 W. Pancake, Liberal, KS 67901

Company to plug at: Hour: 1:15 p.m. Day: 13 Month: 9 Year: 19 90

Plugging proposal received from Tony Harlan

(company name) Chevron U.S.A. Inc. (phone) 713-561-3826

were: 7" at 5041' w/635 sx cement, PBD 4952' Perfs at 4815-4862'

Set cement retainer at 4775'. Load hole with gel, cement with 25 sx through retainer and put 5 sx cement on top of retainer. Perforate 7" casing at 620'. Pump down 7" casing with 180 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 13 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT Set cement retainer at 4775'. Loaded hole with gel. Cemented with 25 sx through retainer and put 5 sx cement on top of retainer. Class A cement.

Perforated 7" casing at 620'. Pumped down 7" casing with 180 sx 65/35 6% gel at 3 1/2 BPM at 350#. Cement circulated out 7"/10% annulus.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 20 1990

Remarks: Cemented by B.J. Services. No casing recovery. CONSERVATION DIVISION  
(If additional description is necessary, use BACK with this Form.)

INVOICED

observe this plugging.

DATE 9-25-90

INV. NO. 29407

9-13

Signed Steve Pfeifer  
(TECHNICIAN)