

1 030419

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,388-0000

NE SE NE, SEC. 19, T 31 S, R 11 W/EX

3630 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Chain Ranch Well # 2-19

Operator: Gear Petroleum Co., Inc.

County Barber 143.98

Name & Address 300 Sutton Place

Well Total Depth 4430 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:45 pm Day: 22 Month: May Year: 19 85

Plugging proposal received from Bill Fulls

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4428' PBD 4403', Perfs at 4365-79'

1st plug sand back to 4310' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 7 sx gel, 1 sack hulls, release 8 5/8" plug and pump 100 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Jack Luthi observed the plugging

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 pm Day: 22 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4310' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement,

7 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

STATE CORPORATION COMMISSION

MAY 31 1985

5-31-85

CONSERVATION DIVISION
WICHITA, KANSAS

Maximum pressure 700 psi and shut in 500 psi Rec 300'

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

INVOICED

If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 6-6-85

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 8343

5-22