

1041330

TO: STATE CORPORATION COMMISSION 12-22 API NUMBER 15-007-10,329-0001
C W/2 NE/4 SEC. 28, T 33 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MCKEE "OWWO" WELL # 2

TECHNICIAN'S PLUGGING REPORT COUNTY BARBER 158.93

OPERATOR LICENSE # 3273 WELL TOTAL DEPTH 4890 FEET

OPERATOR: HERMAN L. LOEB PRODUCTION CSG: SIZE 7" @ 4513' WITH 500 SX

NAME AND PO BOX 524 SURFACE CASING: SIZE 13" @ 279' WITH 250 SX

ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187, MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 9:15 AM DAY: 22 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 3868-90' CEMENT RETAINER @ 4500'

1ST PLUG SPOTTED 25 SX CEMENT AND 100# HULLS AT 3865' THRU TUBING IN 7" CASING.

SPOTTING PLUGS THRU TUBING; INSIDE OF 7" CASING. 2ND PLUG AT 630' WITH 40 SX CEMENT.

3RD PLUG AT 40' WITH 15 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 22 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT _____

PLUGS WERE SPOTTED THRU TUBING; INSIDE OF 7" CASING.

1ST PLUG SPOTTED 25 SX CEMENT AND 100# HULLS AT 3865'.

2ND PLUG AT 630' WITH 40 SX CEMENT.

3RD PLUG AT 40' WITH 15 SX CEMENT.

REMARKS: USED COMMON CEMENT BY ALLIED. NO CASING RECOVERED.

*7" CASING PREVIOUSLY CEMENTED ON BACK SIDE FROM 622' TO SURFACE WITH 240 SX CEMENT.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer
(TECHNICIAN) FORM CE-2/3

DEC 29 1998
60491

12-28-98

