

9-10 15-007-10329-0000

To: 1 040460
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA

W/2 NE, SEC. 28, T 33 S, R 13 W/2E

3960 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519

Lease Name McKee Well # 2

Operator: Chevron U.S.A. Inc.

County Barber 158.92

Name & Address P.O. Box 36366

Well Total Depth 4890 feet

Houston, TX 77236

Conductor Pipe: Size feet

Surface Casing: Size 13 feet 279

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Dunnam Well Service License Number 9678

Address 130 W. Pancake, Liberal, KS 67901

Company to plug at: Hour: 8 a.m. Day: 10 Month: 9 Year: 19 90

Plugging proposal received from L. Klutts

(company name) Chevron U.S.A. Inc. (phone) 713-561-3826

were: 7" at 4513' w/500 sx cement, Open hole at 4513-4890'

Set cement retainer at 4500', displace hole with gel, pump 70 sx cement through retainer.

Sting out of retainer and pump 5 sx cement on top of retainer. Perforate 7" casing at

620'. Pump down 7" casing with 225 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 9 a.m. Day: 10 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT Set cement retainer at 4500', displaced hole with gel, pumped 70

sx Class A cement through retainer. Stung out of retainer and pumped 5 sx cement on top

of retainer. Perforated 7" casing at 620'. Pumped down 7" casing with 225 sx cement.

7"/13" annulus circulated with cement. Circulated 10 sx cement out in cellar. Rate=

3 BPM @ 75#. Used 65/35 Pozmix 6% gel.

RECEIVED
STATE CORPORATION COMMISSION
9-20-90
SEP 20 1990

Remarks: Cemented by B.J. Services. No casing recovery. CONSERVATION DIVISION
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 9-25-90

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 29404
9-10