

1090214

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,843-0000

C NE SE, SEC. 4, T 33 S, R 14 W
1980 feet from ~~XXX~~ section line
SE Corner of
660 feet from ~~XXX~~ section line
SE Corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Allen Well # 1-4

Operator: Texas Energies, Inc.

County Barber

Name & Address P. O. Box 947

Well Total Depth 5050 164.13 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 950

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Wheatstate Oilfield Services License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 6:00 am Day: 29 Month: July Year: 19 84

Plugging proposal received from Roger Baker

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1020' with 50 sx cement
solid bridge

2nd plug hulls - plug at 40' -- cement to surface with 10 sx cement

4th plug to circulate rat hole with 15 sx cement

5th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by R. Brant Sutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7:30 am Day: 29 Month: July Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 1020' with 50 sx cement, 2nd & 3rd plugs - solid

bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 4th plug to circulate

rat hole with 15 sx cement, 5th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 06 1984
8-6-84

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton No. 827497
(If additional description is necessary, use BACK of this form.)

INVOICED

(If back of this form) observe this plugging.

DATE 8-13-84

Signed R. Brant Sutton
(TECHNICIAN)

INV. NO. 3005
7-29 AUG 22 1984