

1 040323

9-18

74 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION of C SE SW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,248-0000
170' S & 20' E
SEC. 2, T 33 S, R 14 W/2
490 feet from S section line
3280 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3532

Lease Name Angell Well # 7

Operator: CMX, Inc.
Name & Address 1026 Union Center Bldg.
Wichita, KS 67202

County Barber
Well Total Depth 894 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 40

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 West Central, Suite 117, Wichita, KS 67202

Company to plug at: Hour: 7:15 p.m. Day: 18 Month: 9 Year: 19 89

Plugging proposal received from John Armbruster

(company name) Duke Drilling Company, Inc. (phone) 316-793-8366

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 200' with 50 sx cement,

2nd plug at 50' with 15 sx cement.

3rd plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10 p.m. Day: 18 Month: 9 Year: 1989

ACTUAL PLUGGING REPORT Circulation was lost at 890' while ratholing ahead. No surface pipe was set yet. Hole was TD at 894'. Pulled tools out of hole. Had trouble getting tools out of hole. Cellar had washed out. Set 40' of 8 5/8" surface pipe. Cemented 8 5/8" in w/75 sx Halliburton lite w/3% cc & 1/2# flow seal. Finished filling backside and topping out washed out cellar w/28 yards of ready mix w/2% cc.

Re-entered hole. Washed hole back down to 150'-bit plugged with sand-hole caving in.

Remarks: Used Halliburton Lite w/3% cc & 1/2# of flowseal.

(if additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 9-25

Signed Stephen J. Pfeiffer (TECHNICIAN)

INV. NO. 25955

NOV 06 1989 FEB 09 1990

FORM CP-2/3 Rev. 01-84

RECEIVED STATE CORPORATION COMMISSION 9-22-89 SEP 22 1989

CONSERVATION DIVISION (over) Wichita, Kansas

CONTINUED:

Trip out with bit-unplug-washed hole back down to 202'GL and plugged as follows:
(had good returns during plugging operations)

1st plug at 202' with 50 sx cement,

2nd plug at 50' with 15 sx cement,

3rd plug to circulate rathole with 15 sx cement.

FORM MUST BE TYPED
FORM C-1 12/88

State of Kansas

007-22,248-0000

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date September 16, 1989
month day year

170' South & 20' East of
C. SE. SW. Sec. 2.: Twp. 33. S, Rg. 14. X West
* 490' feet from South line of Section
* 3280' feet from East line of Section
(Note: Locate well on Section Plat Below)

OPERATOR: License # 03532
Name: CMX, Inc.
Address: 1026 Union Center Bldg.
City/State/Zip: Wichita, KS. 67202
Contact Person: Douglas H. McGinness, II.
Phone: (316) 269-9052

County: Barber
Lease Name: Angell Well # 7
Field Name: Unknown

CONTRACTOR: License # 5929
Name: DUKE Drilling Co., Inc.

Is this a Prorated Field? yes X no
Target Formation(s): Viola
Nearest lease or unit boundary: 490'
Ground Surface Elevation: 1901' feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 125'
Depth to bottom of usable water: 180'
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 360'
Length of Conductor pipe required: None
Projected Total Depth: 5100'
Formation at Total Depth: Ordovician
Water Source for Drilling Operations:
..... well farm pond X other

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield X Mud Rotary
X Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes

If OAWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

WAS: C-Se-Sw; 660' FBL; 3300' FEL; 660' FLL;
G.L. UNLITIAN

DWR Permit #:
Will Cores Be Taken?: yes X no
If yes, proposed zone:
Exp. 1/18/90 Alt. I Req. -200'

AFFIDAVIT

PUSHER _____
TD _____ FORMATION _____
SURFACE PIPE @ _____ ELEVATION _____
ANHYDRITE _____
STARTING TIME & DATE _____
COMPLETION TIME & DATE _____
1st PLUG @ _____ FT. W/ _____ SX _____
2nd PLUG @ _____ FT. W/ _____ SX _____
3rd PLUG @ _____ FT. W/ _____ SX _____
4th PLUG @ _____ FT. W/ _____ SX _____
RAT HOLE CIRCULATED W/ _____ SX _____
MOUSE HOLE CIRCULATED W/ _____ SX _____
WATER WELL PLUGGED W/ _____ SX _____
CEMENT COMPANY _____
TECHNICIAN _____
TYPE OF CEMENT _____

SPUD
9-17-89

400'-8 5/8"

SD

RECEIVED W


STATE CORPORATION COMMISSION

SEP 22 1989

9-22-89

CONSERVATION DIVISION
Wichita, Kansas

LAW



Spud date: _____

Agent: _____

REMEMBER TO:

- File Drill Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field proration orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.

Mail to: Conservation Division, 200 Colorado Derby Building, 202 W. First St., Wichita, Kansas 67202-1286.