

1 060863

1102

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,139-0000
C NE NE, SEC. 2, T 33 S, R 14 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 7077

4620 feet from S section line
660 feet from E section line

Operator: Bowen Oil & Exploration, Inc.
Name & Address 720 North Main Suite 320
Hutchinson, KS 67501

Lease Name Angell Well # 5-2
County Barber 170.24

Well Total Depth 5238 Viola feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Company, Inc. License Number 5829

Address P. O. Box 18611, Wichita, Kansas 67218

Company to plug at: Hour: 7:30 pm Day: 17 Month: July Year: 19 86

Plugging proposal received from Scott Mason

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1946'
Anhydrite 1940'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at '30' below surface pipe with 40 sx cement

3rd plug from 40' to surface with 10 sx cement

4th plug to circulate rat hole with 15 sx cement. 5th plug to circulate mouse hole with 10 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:00 pm Day: 17 Month: July Year: 1986

ACTUAL PLUGGING REPORT 1st plug at 1940' with 50 sx cement, 2nd plug at 330' with 40 sx cement, 3rd plug from 40-0' with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, and 6th to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Poz with 6% Gel by B. J. Titan.
(If additional description is necessary, use BACK of this form.)

Rec'd - KCC
JUL 23 1986
7-17-86

INVOICED
observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE JUL 23 1986

INV NO. 14420
7-17