

1 060067

3-27

000044 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,358
NE NE SE, SEC. 36, T 33 S, R 13 WAK
2310 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238
Operator: Petroleum, Inc.
Name & Address: 301 N. Main, Suite 900
Wichita, KS 67202

Lease Name Hall "F" Well # 2
County Barber 167.70
Well Total Depth 5160 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 321

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418
Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 10 p.m. Day: 26 Month: 3 Year: 19 91

Plugging proposal received from John Johnson
(company name) Allen Drilling Company (phone) 316-793-5681

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 575'
1st plug at 5100' with 40 sx cement, 2nd plug at 575' with 50 sx cement,
3rd plug at 350' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 4:30 a.m. Day: 27 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 5100' with 40 sx cement,
2nd plug at 575' with 50 sx cement,
3rd plug at 350' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1991
3-29-91
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services.
(if additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 4-9-91
INV. NO. 31421

Signed [Signature] (TECHNICIAN)

NOTICE OF INTENTION TO DRILL Must be approved by the K. C. five (5) days prior to commencing well

Expected Spud Date March 22 1991 NE NE SE Sec 36 Twp 33 S, Rg 13 East West

OPERATOR: License # 5238 Name: Petroleum, Inc. Address: 301 N. Main, Suite 900 City/State/Zip: Wichita, Kansas 67202 Contact Person: R. G. Julius Phone: 316 291-8281

CONTRACTOR: License #: 5418 Name: Allen Drilling Co.

Well Drilled For: Well Class: Type Equipment: Oil ... Inj ... Infield Mud Rotary Gas ... Storage ... Pool Ext. ... Air Rotary OWMO ... Disposal Wildcat ... Cable Seismic; ... # of Holes

If OWMO: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth:

Directional, Deviated or Horizontal wellbore? yes no If yes, total depth location:

2310 feet from South line of Section 330 feet from East line of Section (Notes: Locate well on Section Plat on Reverse Side) County: Barber Lease Name: Hall 'F' well #: 2 Field Name: Driftwood Is this a Prorated Field? yes no Target Formation(s): Arbuckle Nearest lease or unit boundary: 330' Ground Surface Elevation: 1496 feet MSL Domestic well within 330 feet: yes no Municipal well within one mile: yes no Depth to bottom of fresh water: 100' Depth to bottom of usable water: 180' Surface Pipe by Alternate: 1 ... 2 Length of Surface Pipe Planned to be set: 300' Length of Conductor pipe required: 0 Projected Total Depth: Arbuckle Formation at Total Depth: 5200' Water Source for Drilling Operations: well farm pond other creek DWR Permit #: Will Cores Be Taken?: yes no If yes, proposed zone:

Exp. 9/14/91 AFFIDAVIT 200' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with the provisions of the Kansas Oil and Gas Conservation Commission et. seq. It is agreed that the following minimum requirements will be met:

Pusher John Johnson INIT. CM
 SPUD DATE 3-15-91
 LENGTH SURFACE PLANNED 300'
 RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.
 RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE @ 2 1/2" CONDUCTOR ANHYDRITE T- B- 5752 ELEVATION
 TD 5160' FORMATION
 RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
 Arbuckle Plug @ 2 Ft. W/ 40 SX
 Hug./Council @ 5100 Ft. W/ SX
 Anhydrite Base @ 575 Ft. W/ 50 SX
 1/2 Base Anyh. @ SX Ft. W/ SX
 1/2, 1/2 Plug @ SX Ft. W/ SX
 Bottom Surface @ 350 Ft. W/ 50 SX
 40' Plug @ 40 Ft. W/ 10 SX
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
 WATER WELL SX (Irr. Well) Pond Hauling
 TECHNICIAN CM DATE 3-22-91
 TYPE OF CEMENT 60/40 67
 STARTING TIME 10:00 (AM/PM) DATE 3-26-91
 COMPLETION TIME 4:30 (AM/PM) DATE 3-27-91
 CEMENT COMPANY OS Services

RECEIVED STATE OIL AND GAS CONSERVATION COMMISSION 3-29-91 MAR 29 1991

CERTIFICATION OF WORK