

To: 2 040344
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5038

Operator: Robinson Oil Co.

Name & Address 737 RH Garvey Bldg.

Wichita, KS 67202

7-15-87
API NUMBER 15-077-20306-00-00

C. NW SE, SEC. 17, T 34 S, R 9 W 1/4 X

1980 feet from S section line

1980 feet from E section line

Lease Name Vondracek- Well # 1
Cantrell

County Harper 150.22

Well Total Depth 4622 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well Gas Well ☒ Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, KS

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Dallas

(company name) Kelso Casing Pulling (phone)

were: Sand 50' above open hole, Shoot pipe, Pump 3 sxs hulls, 15 sxs gel,

100 sxs 60/40 4% gel

4 1/2" @4609, PBTD 4617 Open hole 4609-4617

Plugging Proposal Received by District #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part ☒ None

Operations Completed: Hour: 18:00 Day: 15 Month: 7 Year: 1987

ACTUAL PLUGGING REPORT Sand was dumped inside the 4 1/2" casing to 4550 and capped

with 4 sxs of cement. The 4 1/2" casing was shot off and recovered from

approximately 3900'. The top was squeeze plugged through the 8 5/8"

casing by pumping 300# of hulls, 15 sxs of gel and 100 sxs of 60/40 poz 4% gel.

Remarks: Allied #2470 MX 500# SI 500#
(If additional description is necessary, use BACK of this form.)

INVOICED
(If desired, observe this plugging.)

DATE 7-22-87

INV. NO. 12598
7-15

Signed *Steve A. Lewis*
(TECHNICIAN)