

1041335

TO: STATE CORPORATION COMMISSION 1-25

API NUMBER 15-007-10,310-0001  
50' W C NE SEC. 20, T 33 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1370 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MCKEE "OWWO" WELL # 6

TECHNICIAN'S PLUGGING REPORT

COUNTY BARBER 150.51

OPERATOR LICENSE # 3273

WELL TOTAL DEPTH 4631 FEET

OPERATOR: HERMAN L. LOEB

PRODUCTION CSG: SIZE 7" @ 4535' WITH 550 SX

NAME AND PO BOX 524

SURFACE CASING: SIZE 10 1/4" @ 291' WITH      SX

ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL      GAS WELL      INPUT WELL      SWD WELL      D/A X

OTHER WELL AS HEREINAFTER INDICATED     

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187, MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 25 MONTH: 01 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 4423-29' (CIBP @ 4400') PERFS @ 3882-88'

1ST PLUG AT 3867' WITH 35 SX CEMENT.

2ND PLUG AT 630' WITH 25 SX CEMENT.

3RD PLUG AT 300' WITH 25 SX CEMENT.

4TH PLUG AT 40' WITH 15 SX CEMENT. PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART      NONE     

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 25 MONTH: 01 YEAR: 1999

ACTUAL PLUGGING REPORT     

1ST PLUG SPOTTED 35 SX COMMON CEMENT IN 7" CASING THRU TUBING @ 3860'.

SPOT PLUGS INSIDE OF 7" CASING THRU 2 7/8" TUBING.

2ND PLUG AT 630' WITH 25 SX CEMENT. 3RD PLUG AT 300' WITH 25 SX CEMENT.

4TH PLUG AT 40' WITH 15 SX CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 27 1999  
1-27-99  
CONSERVATION DIVISION  
Wichita, Kansas

REMARKS: USED COMMON CEMENT BY ALLIED. NO CASING RECOVERED.

NOTE: OCT 9, 1991 WHEN WELL WAS PLUGGED-DUG OUT 10 1/4 X 7" ANNULAS AND FOUND CMT. TO SURFACE ON BACKSIDE OF 7" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Penner  
(TECHNICIAN) FORM CP-2/3

1-28-99  
60588