

1 040463

9-11

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-10.308 -0000

C SW, SEC. 20, T 33 S, R 13 W&E

1320 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519

Lease Name Lasswell Well # A-1

Operator: Chevron U.S.A. Inc.

County Barber 152.88

Name & Address P.O. Box 36366

Well Total Depth 4704 feet

Houston, TX 77236

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 280

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Dunnam Well Service License Number 9678

Address 130 W. Pancake, Liberal, KS 67901

Company to plug at: Hour: 1 p.m. Day: 11 Month: 9 Year: 19 90

Plugging proposal received from Tony Harlan

(company name) Chevron U.S.A. Inc. (phone) 713-561-3826

were: 7" at 4704' w/550 sx cement, PRTD 4703' Perfs at 4658-84'

Oct. of 1986-hole in casing at 865-960' was successfully squeezed w/260 sx Class A cement.

Set cement retainer at 4600', pump 20 sx cement through retainer and put 5 sx cement on top.

Perforate 7" casing at 620', load 7" casing w/water, perforate 7" casing at 250', pump 100

sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 p.m. Day: 11 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT Set cement retainer at 4600', pumped 20 sx cement through retainer

and put 5 sx cement on top of retainer. Class A cement. Maximum pressure 400 psi. Hole

loaded with gel from bottom plug to surface. Perforated 7" casing at 620'. Loaded 7"

casing with water. Pressured to 400#. Couldn't pump into. Perforated 7" casing at 250'.

Pumped down 7" casing with 100 sx 65/35 6% gel cement at 3 BPM at 100#. Cement circulated

out 7"/10 3/4 annulus.

Remarks: Cemented by B.J. Services. No casing recovery.

(If additional description is necessary, use BACK of this Form.)

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1990
9-20-90
CONSERVATION DIVISION
Wichita, Kansas

INVOICED observe this plugging.

Signed Steve Pfeifer (TECHNICIAN)

DATE 9-25-90

INV. NO. 29409

9-11