

15-007-10315-00-01

1031533

TO: STATE CORPORATION COMMISSION  
API NUMBER NA  
C NW SEC. 21, T 33 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MCKEE WELL # 5

TECHNICIAN'S PLUGGING REPORT COUNTY BARBER

OPERATOR LICENSE # 3273 WELL TOTAL DEPTH 4400 FEET

OPERATOR: HERMAN L. LOEB PRODUCTION CSG: SIZE 7" @ 4575' WITH 550 SX

NAME AND PO BOX 524 SURFACE CASING: SIZE 10 1/4" @ 286' WITH SX

ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187 MEDICINE LODGE, KS 67104-0187

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 23 MONTH: 11 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM GEORGE PAYNE

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: IN 1992 PERFORATED AND SQUEEZED WELL AT 620'. CIRCULATED TO SURFACE WITH 185 SX.

RAN 2 3/8" TUBING DOWN HOLE TO 4030'. 1ST PLUG AT 4030' WITH 30 SX CEMENT.

2ND PLUG AT 600' WITH 95 SX CEMENT. CIRCULATED CEMENT TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 23 MONTH: 11 YEAR: 1999

ACTUAL PLUGGING REPORT \_\_\_\_\_

RAN 2 3/8" TUBING DOWN HOLE TO 4030'. 1ST PLUG AT 4030' WITH 30 SX CEMENT.

2 ND PLUG AT 600' WITH 950 SX CEMENT. CEMENT CIRCULATED TO SURFACE.

RECEIVED  
KANSAS CORPORATION COMMISSION

533 09 1999  
12-8-99

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID NOT) RESERVE THIS PLUGGING.

SIGNED Steve Durrant  
(TECHNICIAN)

FORM CP-2/3

DATE 12/21/99

NO. NO. 27993

(12)