

9-12

To: 1 040464
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19-NA 15-007-10315-0000

C NW, SEC. 21, T 33 S, R 13 ~~W~~

3960 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519

Lease Name McKee Well # 5

Operator: Chevron U.S.A. Inc.

County Barber 152.55

Name & Address P.O. Box 36366

Well Total Depth 4694 feet

Houston, TX 77236

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 286

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hayes Well Service License Number 5429

Address P.O. Box 108, Attica, KS 67009

Company to plug at: Hour: 11 a.m. Day: 12 Month: 9 Year: 19 90

Plugging proposal received from L. Klutts

(company name) Chevron U.S.A. Inc. (phone) 713-561-3826

were: 7" at 4575' w/550 sx cement, Open hole at 4575-4694'

Set cement retainer at 4550'. Load hole with gel. Cement with 25 sx through retainer and

5 sx cement on top. Perforate 7" casing at 620'. Pump 185 sx cement down 7" casing.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1 p.m. Day: 12 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT Set cement retainer at 4550'. Loaded hole with gel. Cemented

with 25 sx cement through retainer and put 5 sx cement on top of retainer. Class A cement.

Perforated 7" casing at 620'. Broke circulation. Pumped 185 sx 65/35 6% gel down 7" casing.

7"/10 3/4" annulus circulated with cement. Rate=1 1/2 BPM at 75-100#.

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1990
9-20-90

Remarks: Cemented by B.J. Services. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 9-25-90

Signed Steve Pfeifer
(TECHNICIAN)

INV. NO. 29403

9-12