

To: 1 040462
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-11
API NUMBER 13- 007-10,313-0000
120' W of
C N/2 NE, SEC. 21, T 33 S, R 13 W/4E
4620 feet from S section line
1440 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519

Lease Name McKee Well # 3

Operator: Chevron U.S.A. Inc.
Name

County Barber 150.89

Address P.O. Box 36366

Well Total Depth 4643 feet

Houston, TX 77236

Conductor Pipe: Size feet

Surface Casing: Size 13 feet 273

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Hayes Well Service License Number 5429

Address P.O. Box 108, Attica, KS 67009

Company to plug at: Hour: 8 a.m. Day: 11 Month: 9 Year: 19 90

Plugging proposal received from L. Klutts

(company name) Chevron U.S.A. Inc. (phone) 713-561-3826

were: 7" at 4550' w/500 sx cement, 5 1/2" liner at 4479-4641'-slotted, Perfs at 4550-4641'
PBTD 4641'

Cement retainer set at 4450'. Pump 35 sx cement through retainer and put 5 sx cement on top of retainer. Load hole with gel from bottom plug to surface. Perforate 7" casing at 620'. Pump down 7" casing with 210 sx cement.

Plugging Proposal Received by Stephen J. Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 11 a.m. Day: 11 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT Set cement retainer at 4450'. Pumped 35 sx cement through retainer and put 5 sx on top of retainer. Maximum pressure 750 psi. Class A cement.

Hole loaded with gel from bottom plug to surface. Perforated 7" casing at 620'. Pumped down 7" casing with 210 sx 65/35 6% gel cement at 3 BPM at 200#. Cement circulated out 7"/13" annulus.

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1990
9-20-90
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Cemented by B.J. Services. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED (Do not X out) observe this plugging.

Signed Stephen J. Pfeifer
(TECHNICIAN)

DATE 9-25-90

INV. NO. 29410

9-11