

To: 1 041227  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 007-22,399-00-00  
NW SW SE, SEC. 27, T 30 S, R 12 W/E  
990 feet from S section line  
2310 feet from E section line

12-26

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5030  
Operator: Vess Oil Corporation  
Name & Address: 8100 E. 22nd St. N, Bldg. 300  
Wichita, KS 67226

Lease Name Mease Well # 1  
County Barber 151.87  
Well Total Depth 4673 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 a.m. Day: 26 Month: 12 Year: 19 96

Plugging proposal received from Alan Vratil  
(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4666' w/175 sx cement, Open hole 4666-73'

1st plug sand back to 4600' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, release 8 5/8" wiper plug  
and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None   
Operations Completed: Hour: 11 a.m. Day: 26 Month: 12 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 4520' and dumped 5 sx cement on top of sand  
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 1350 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I did not observe this plugging.

DATE JAN 06 1997  
INV. NO. 47278

Signed *Steve Pfeifer* (TECHNICIAN)