

1041399

TO: STATE CORPORATION COMMISSION

API NUMBER 15-007-22,389-00-00  
NE NE SW SEC. 27, T 30 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SPICER WELL # 3  
COUNTY BARBER 152.91

TECHNICIAN'S PLUGGING REPORT 6/16

OPERATOR LICENSE # 5030 WELL TOTAL DEPTH 4705.5 FEET

OPERATOR: VESS OIL CORPORATION PRODUCTION CSG: SIZE 4 1/2" @ 4701' WITH 300 SX

NAME AND 8100 E 22ND N BLDG 300 SURFACE CASING: SIZE 8 5/8" @ 310' WITH 170 SX

ADDRESS WICHITA, KS 67226

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ INJ WELL \_\_\_\_\_ D/A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 12:15 PM DAY: 16 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MONTE ANDREWS RECEIVED STATE CORPORATION COMMISSION

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945 JUN 30 2000

WERE: ARBUCKLE OPEN HOLE AT 4701-4705.5 CONSERVATION DIVISION

SANDED BACK TO 4540' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER. LOAD HOLE Wichita, Kansas

WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 700' WITH 50 SX CEMENT. 2ND PLUG

AT 320' WITH 40 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 16 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT \_\_\_\_\_

SANDED BACK TO 4540' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER. LOAD HOLE

WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 700' WITH 50 SX CEMENT. 2ND PLUG

AT 320' WITH 40 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2710' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED SIGNED  
DATE 7/5/00  
WV. NO. 1060017

Stephen J. Pfeifer SA  
(TECHNICIAN) FORM CE-2/3

