

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22382-00-00
Spot: SESENW Sec/Twnshp/Rge: 27-30S-12W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease/Unit Name: CARGILL G Well Number: 1
County: BARBER Total Vertical Depth: 4706 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 SOUTH MAIN - SUITE 505
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 233 WITH 170 SX CMT
Production: Size 4.5 feet: 4685 WITH 275 SX CMT *152.95*
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2001 3:15 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: RON SMITH Company: PICKRELL DRILLING Phone: (316) 262-8427

Proposed Plugging Method: CIBP @ 3975'. 1ST PLUG AT 700' WITH 50 SX CMT. 2ND PLUG AT 260' WITH 40 SX CMT. 3RD PLUG AT 0-40' WITH 10-15 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/07/2001 4:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4428'. PERFS AT 4032-35. CIBP @ 4228'. PERFS AT 4284-94. CIBP @ 4428 & 4528'. PERFS AT 4571-75. ARBUCKLE OPEN HOLE. SQUEEZED @ 4685-4706.5'. SET CIBP @ 3975' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LOAD HOLE WITH GEL & SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 700' WITH 50 SX CMT. 2ND PLUG AT 260' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 2001

6-18-01

CONSERVATION DIVISION

INVOICED

DATE 6-18-01

INV. NO. 2001061959

Remarks: USED COMMON CEMENT BY ALLIED. RECOVERED 2650' OF 4 1/2".

Plugged through: CSG

District: 01

Signed Stephen J Pfeifer
(TECHNICIAN)

JUN 11 2001

Form 202/3