

4-24

To: 1 120248  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-21,970-00-00  
C NW NE, SEC. 27, T 30 S, R 12 WAK  
4620 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5047  
Operator: Rupe Oil Company, Inc. Lease Name Meairs "A" Well # 1  
Name & Address P.O. Box 2273 Barber 125.48  
Wichita, KS 67201  
Well Total Depth 3861 feet  
Conductor Pipe: Size \_\_\_\_\_ feet

RECEIVED  
STATE CORPORATION COMMISSION  
APR 26 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_  
Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1 p.m. Day: 24 Month: 4 Year: 19 89

Plugging proposal received from Elmo Morgenstern  
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 3864' PBD 3760' Perfs at 3704-10'  
1st plug sand back to 3650' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 24 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3650' and dumped 4 sx cement  
on top of sand through bailer,  
2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement,  
Pumping pressure 0-700 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2400' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 5-3-89  
INV. NO. 24583

Signed Deane Rankin  
(TECHNICIAN)