

1041402

TO: STATE CORPORATION COMMISSION

API NUMBER 15-007-21,422-00-00
SE SW SEC. 27, T 30 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SPICER WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY BARBER 157.35

OPERATOR LICENSE # 5030

WELL TOTAL DEPTH 4657 FEET

OPERATOR: VESS OIL CORPORATION PRODUCTION CSG: SIZE 4 1/2" @ 4645' WITH 230 SX

NAME AND 8100 E 22ND N, BLDG 300 SURFACE CASING: SIZE 8 5/8" @ 333' WITH 200 SX

ADDRESS WICHITA, KS 67226

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ INJ WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 20 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MONTE ANDREWS

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 3749-3753

SAND BACK TO 3620' & PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 700' WITH 50 SX CEMENT. 2ND PLUG AT 360' WITH 40 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 20 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT _____

SAND BACK TO 3620' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER.

LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 700' WITH 50 SX CEMENT.

2ND PLUG AT 360' WITH 40 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3200' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING. DATE 7/18/00 SIGNED _____

Stephen J. Pfeifer
(TECHNICIAN)

INV. NO. 1060077

FORM CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
7-14-00
JUL 14 2000
CONSERVATION DIVISION
WICHITA, KANSAS