

1 080518

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,128-00-00
75' N W/2
NW SE , SEC. 23 , T 30 S, R 12 W 1/2
2055 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5047
Operator: Rupe Oil Company
Name & Address: P. O. Box 2273
Wichita, KS 67201

Lease Name Kumberg "D" Well # 1
County Barber 147.88
Well Total Depth 4550 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rupe Energy, Inc. License Number 8752
Address P. O. Box 2273, Wichita, KS 67201

Company to plug at: Hour: 10:00 am Day: 29 Month: April Year: 19 86

Plugging proposal received from Bill Gallaugher
(company name) Rupe (phone) 316-262-3748

were: 4 1/2" at 4522' PBTD 4436' Perfs at 4392-4402' & 4364-74'
1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:45 am Day: 29 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10
sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 250 psi and shut in 150 psi

Remarks: Recovered 3510' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
MAY 05 1986
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

DATE MAY 06 1986

Signed J. N. Mead
(TECHNICIAN)

INV. NO. 13656

4-29 MAY 28 1986