

9-25-87

To: 1 070440
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,166-0000
Appr. NW NW NW, SEC. 24, T. 30 S, R. 12 W/EX
4900 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5923

Lease Name Kumberg Well # 1
County Barber 149.18
Well Total Depth 4590 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 246

Operator: American Petroleum Company, Inc.
Name & Address 3500 North Rock Road, Bldg. 1300
Wichita, KS 67226

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling Inc. License Number 5380
Address Box 8609, Wichita, KS 67208

Company to plug at: Hour: 8:15 p.m. Day: 25 Month: 9 Year: 1987

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling Inc. (phone) 316-945-9935
Elevation 1771'

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 670-700'
1st plug at 700' with 50 sx cement, 2nd plug at 30' below base of surface pipe with
40 sx cement, 3rd plug at 40-0' with 10 sx cement,
4th plug to circulate rathole with 10 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10 p.m. Day: 25 Month: 9 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 700' with 50 sx cement,
2nd plug at 300' with 40 sx cement,
3rd plug at 40-0' with 10 sx cement,
4th plug to circulate rathole with 10 sx cement,
5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
10-16-87
OCT 16 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

Signed Dan Gooden
(TECHNICIAN)

DATE 10-19-87

INV. NO. 18551