

To: 1 010119
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,061-00-00
100' E OF
SE SW SW, SEC. 26, T 30 S, R 12 W/E
330 feet from S section line
4390 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087
Operator: Texas Energies, Inc.
Name & Address: P. O. Box 947
Pratt, KS 67124

Lease Name: Meairs Well # 1-26
County: Barber 145.28
Well Total Depth: 4470 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Kelso Casing Pulling License Number 6050

Address: P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:10 am Day: 20 Month: March Year: 19 86

Plugging proposal received from: Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4438' PBSD 4395' Perfs at 4298-4303'
1st plug sand back to 4245' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 100 sx cement

Plugging Proposal Received by: Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:05 pm Day: 20 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4240' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10
sx gel, 1 sack hulls and 100 sx cement (no plug - did not have container).

Maximum pressure 600 psi and shut in 500 psi

Remarks: Recovered 3600' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
I did / was not serve this plugging.

DATE APR 1 1986

STATE CORPORATION COMMISSION Signed: *Joel L. Gault* (TECHNICIAN)

INV. NO. 13219

MAR 31 1986
3-31-86
CONSERVATION DIVISION