

1041356

TO: STATE CORPORATION COMMISSION

6.30

API NUMBER 15-007-22,518-00-00
W/2 W/2 SW SEC. 22, T 30 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4950 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CARGILL WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY BARBER 154.38

OPERATOR LICENSE # 31881

WELL TOTAL DEPTH 4750 FEET

OPERATOR: MCGINNESS OIL COMPANY OF KS PRODUCTION CSG: SIZE 5 1/2" @ 4749' WITH 275 SX

NAME AND 150 N MAIN, SUITE 1026 SURFACE CASING: SIZE 8 5/8" @ 313' WITH 200 SX

ADDRESS WICHITA, KS 67202 CONDUCTOR CSG: SIZE 13 3/8" @ 55' WITH 60 SX

ABANDONED OIL WELL GAS WELL X INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31528

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 30 MONTH: 06 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4633-35 CIBP @ 4234, 4135-37, 3531.5-3215, CIBP @ 3600

PUMP DOWN 5 1/2" CASING WITH 30 SX COMMON CEMENT WITH 3% CC. STOP PLUG AT 3060'. SHUT IN

PRESSURE AT 3300#. COMPLETED BY ALLIED. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL -

50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG AND 100 SX CEMENT. MAXIMUM PSI

AT 600#. SHUT IN WITH 500#.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:00 AM DAY: 30 MONTH: 06 YEAR: 1999

ACTUAL PLUGGING REPORT

PUMPED DOWN 5 1/2" CASING WITH 30 SX COMMON CEMENT WITH 3% CC. STOP PLUG AT 3060'. SHUT IN

PRESSURE 3300# BY ALLIED. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT -

10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG AND 100 SX CEMENT. MAXIMUM PRESSURE AT 600#.

SHUT IN WITH 500#.

JUL 7-6-99

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES, LLC. RECOVERED 2500' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED

DATE 7-9-99
INV. NO. 60019

SIGNED [Signature] (TECHNICIAN) FORM CP-2/3

[Signature]