

1 040037

12-29-87

API NUMBER 15- 007-21,427-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 80' W C SE SW, SEC. 22, T 30 S, R 12 W EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

660 feet from S section line

3380 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Cargill Well # 1-22

Operator: Texas Energies, Inc.

County Barber 150.80

Name & Address P.O. Box 947

Well Total Depth 4640 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 342

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 647, Chase, KS 67524

Company to plug at: Hour: 7:45 a.m. Day: 29 Month: 12 Year: 19 87

Plugging proposal received from Ted Moff

(company name) Kelso Casing Pulling (phone) 316-672-7838

were: 4 1/2" at 4227' PBD 3800' Perfs at 2933-36, 3718-20'

1st plug sand back to 2880' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 8 p.m. Day: 29 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 2880' and dumped 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, and 5 sx gel. Locked up at 1200 psi.

Shut down. Maximum pressure 1200 psi and shut in 1200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If possible) observe this plugging.

DATE 1-11-88

INV. NO. 19516

Signed Stephen P. Plifis (TECHNICIAN)