

8-31

2-040651

209
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-21,247-00-00

SE NW, SECTION 4 TOWNSHIP 33 RANGE 7W

OPERATOR LICENSE # 30739

3300 FEET FROM S SECTION LINE
3730 FEET FROM E SECTION LINE

OPERATOR Deka Exploration
NAME & P. O. Box 14057
ADDRESS Oklahoma City, OK 73114

LEASE NAME: Butler #1 161.42
COUNTY: Harper
WELL TOTAL DEPTH: 4967'

CONDUCTOR PIPE: " @ ' "

SURFACE CASING: 8-5/8" @ 293'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Allen Drilling
ADDRESS: Great Bend, KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: J. Johnson
COMPANY NAME: Allen Drilling PHONE: _____

WERE: 35 sx @ 1300' - 35 sx @ 900' - 35 sx @ 350' - 25 sx @ 60' - 10 sx RH

PLUGGING PROPOSAL RECEIVED BY: Ralph Tittel

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: _____ DAY: 31 MONTH: 8 YEAR: 1991

ACTUAL PLUGGING REPORT:
Drill pipe run open ended to 1300' & 35 sx cmt spotted - drillpipe pulled to 900' & 35 sx cmt spotted - drl pipe pulled to 350' & 35 sx cmt spotted - drill pipe pulled to 60' & cmt circ to surf - rat hole circ with 10 sx cmt.

REMARKS: Allied Cement 40/60 poz 4% gel

INVOICED (DO NOT RESEAL THIS PLUGGING.)

DATE 11-8-91

WEL. NO. 33648

8-31

Steve Van Gieson
Steve Van Gieson (AGENT)

dw