

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-20,932-00-00
NW NW, SECTION 29 TOWNSHIP 32 RANGE 8W

OPERATOR LICENSE # 31289 4620 FEET FROM S SECTION LINE
4620 FEET FROM E SECTION LINE

OPERATOR NJRE OPERATING COMPANY
NAME & 15 W 6TH STREET, STE 2400
ADDRESS TULSA, OK 74119

LEASE NAME: SANDERS E-2
COUNTY: HARPER
WELL TOTAL DEPTH: 3900' *CB 3855'*

CONDUCTOR PIPE: _____
SURFACE CASING: 8-5/8" @ 253'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: CLARKE CORP
ADDRESS: MEDICINE LODGE KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: BOB CARPENTER

COMPANY NAME: NJRE OPERATING CO PHONE: _____

WERE: 4-1/2" @ 3899' - 3677-94' - PBDT 3855' - SET CIBP @
3675 & 2 SX - 35 SX @ 1300' - 35 SX 850' - CIRC CMT
300' TO 0'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 16:30 DAY: 8 MONTH: 12 YEAR: 1993

ACTUAL PLUGGING REPORT:
CIBP SET @ 3625' & CAPPED W/2 SX CMT - THIS CLOSED
OFF THE STALNAKER PERFS - 4-1/2" WAS REC 2147' &
PULLED FROM WELLBORE - TUB RUN BACK IN WELLBORE TO
1300' WHERE 35 SX CMT SPOTTED - TUB PULLED TO 862' &
WHERE 35 SX CMT SPOTTED - TUB PULLED TO 307' & CMT CIRC
TO SURF - REMAINING TUB PULLED FROM WELLBORE & CMT
BROUGHT BACK TO SURF.

REMARKS: ALLIED CLASS "A" #3508

RECEIVED
KANSAS CORPORATION COMMISSION

INVOICED
I HAVE OBSERVED THIS PLUGGING.

DATE 12-30-93

INV. NO. 39599

15/
STEVE VAN GIESON (AGENT)

DEC 22 1993

CONSERVATION DIVISION
WICHITA, KANSAS

12-8 FEB 23 1994

MAR 15 1994